TECHNICAL AND FINANCIAL BID

Bidder: Sunrise Energy Systems Pvt Ltd

Tender No.: PMC/ELEC/2026/0417

Name of Work: Supply, Installation & Commissioning of Grid-Connected Rooftop Solar PV Systems at Municipal Buildings

Submitted to: The Executive Engineer (Electrical), Pune Municipal Corporation

Date: 03-02-2026

Authorised Signatory: Anil Kulkarni, Director

Form A - Covering Letter

We, Sunrise Energy Systems Pvt Ltd, hereby submit our bid for the above work. We have read and understood all terms and conditions of the tender document and accept them unconditionally.

Our bid shall remain valid for 120 days from the date of opening of technical bids.

Section 1 - Company Profile

Sunrise Energy Systems Pvt Ltd was incorporated in 2011 and is headquartered in Pune, Maharashtra. The company designs and builds rooftop solar PV systems for industrial, institutional and municipal clients.

CIN: U40106PN2011PTC139876. PAN: AAAFS1234C.

Annexure B - Financial Statements

Our audited financial statements for FY2022-23 to FY2024-25 show an average annual turnover of Rs. 6,10,00,000/-.

Turnover for FY 2022-23, FY 2023-24 and FY 2024-25 was Rs. 5.20 Crore, Rs. 6.05 Crore and Rs. 7.05 Crore respectively.

Audited balance sheets signed by M/s Joshi and Associates, Chartered Accountants, are enclosed.

Section 2 - Organisation and Resources

We employ 64 permanent staff, including design engineers, supervisors and trained technicians, working from offices in Pune and Nashik.

Section 3 - Past Projects

We completed the 500 kW rooftop solar installation for XYZ Textiles Ltd, Bhiwandi in 2023, valued at Rs. 2.3 Crore.

We also commissioned a 120 kW rooftop solar system for Shree Hospital, Nashik in 2021, valued at Rs. 68 Lakh.

Completion letters from both clients are enclosed in Annexure F.

Section 4 - Commercial Proposal

Complete supply, installation and commissioning will be delivered within 75 days of work order issuance.

We accept the payment terms specified in Clause 4.2 of the tender document without deviation.

Section 5 - Technical Specifications

We offer a comprehensive warranty of 12 years on the complete system, covering panels, inverters and workmanship.

Modules offered are 545 Wp mono-PERC conforming to IEC 61215 and IEC 61730.

Section 6 - Technical Team

Mr. Rahul Deshmukh, Certified Electrical Engineer (License No. EE/2019/4521), will be deployed full-time at the project site.

He will be supported by two supervisors and a team of twelve trained technicians.

Methodology

Our execution methodology follows a design-first approach: a detailed site survey, shadow analysis and structural assessment of each roof precede the final layout.

Material is dispatched only after design approval by the Engineer-in-Charge, which avoids rework at site.

Project Schedule

Weeks 1 and 2 cover site survey and design approval. Weeks 3 to 6 cover procurement. Weeks 7 to 10 cover installation, and week 11 covers testing and handover.

Quality Assurance Plan

Every lot of modules and inverters is inspected on receipt against the approved datasheets. Torque values, cable routing and earthing continuity are checked and recorded for every building.

Health, Safety and Environment

All rooftop work is carried out with fall-arrest systems and edge protection. A toolbox talk is held at the start of every shift and recorded in the site register.

Operation and Maintenance Plan

Modules are cleaned fortnightly and inverters are inspected monthly. Breakdown complaints are attended within 48 hours of being reported.

Training Plan

Two half-day sessions will be conducted for PMC staff covering safe isolation, daily monitoring and basic fault identification.

Organisation Chart

The project is led by a Project Manager who reports to a Director. Site execution is handled by a site-in-charge supported by supervisors and technicians.

List of Tools and Equipment

Insulation resistance tester, earth resistance tester, clamp meter, IV-curve tracer, thermal camera, torque wrenches and safety harnesses.

Compliance Statement

We confirm compliance with the technical specifications in Section 7 of the tender document without deviation.

Declaration

We declare that our firm has not been debarred by any government department or public sector undertaking as on the date of this bid.

Power of Attorney

The Board of Directors has authorised the undersigned to sign and submit this bid and all related documents on behalf of the company.

Client List

Our clients include textile units, hospitals, educational institutions, dairies and housing societies across Maharashtra.

Annexure C - Statutory Compliance

GST Registration Certificate enclosed as Annexure C, GSTIN 27AAAFS1234C1Z5.

Legal name: Sunrise Energy Systems Private Limited. Principal place of business: Pune.

Annexure D - Labour Registrations

EPF Registration No. MH/PUN/0098765 and ESIC Registration No. 33-00-112233 are enclosed as Annexure D.

Methodology

Our execution methodology follows a design-first approach: a detailed site survey, shadow analysis and structural assessment of each roof precede the final layout.

Material is dispatched only after design approval by the Engineer-in-Charge, which avoids rework at site.

Annexure E - Manufacturer Authorization

Authorization letter from panel manufacturer Waaree Energies Ltd, dated 20-01-2026, is enclosed as Annexure E.

Project Schedule

Weeks 1 and 2 cover site survey and design approval. Weeks 3 to 6 cover procurement. Weeks 7 to 10 cover installation, and week 11 covers testing and handover.

Bill of Quantities

Item	Amount
Supply of PV modules and inverters	Rs. 27,40,000/-
Mounting structures and balance of system	Rs. 9,10,000/-
Installation, testing and commissioning	Rs. 6,00,000/-

All rates are inclusive of GST and freight to site.

Financial Bid - Form B Price Schedule

Our total quoted price for the complete scope of work, inclusive of all taxes and duties, is Rs. 42,50,000/- (Rupees Forty Two Lakh Fifty Thousand only).